



NOTES

1. ALL GROUNDING POINTS SHALL BE TIED TOGETHER.
2. GROUND RODS: 5/8" x 8'-0" COPPER CLAD STEEL WITH 25 OHM OR LESS RESISTANCE (3 MIN. REQUIRED)
3. GROUND WIRE: NO. 6 BARE SOLID COPPER WIRE
4. CONTRACTOR SHALL PROVIDE GROUNDING TEST RESULTS TO THE CITY.



HISTORIC  
FRANKLIN  
TENNESSEE

**TRAFFIC SIGNAL CABINET GROUNDING**

CITY OF FRANKLIN

NOT TO SCALE

CITY  
ENGINEER:

*Paul P. Hoyle*

DATE:

7/1/2020

DWG. NO.

**ITS-4**